500 x 500 mm Linear Carpet Tiles with PVC Backing

Product Specification Schedule

Selected module	500 x 500 mm; 0.25 m2 before cuts
Configuration options	PVC backing 6 mm total 500 x 500 mm PP face; Asphalt backing 5 mm total 500 x 500 mm PP face
Selected textile face	Polypropylene; taupe linear visual direction
Build-up alternatives	PVC backing: 6 mm total / asphalt backing: 5 mm total
Laying directions	Monolithic same direction or alternating quarter-turn
Area calculation	4 full tiles per m2 before cuts and spares
Separate installation items	Adhesive/tackifier, underlay, transitions and installation only when listed
Specified application	Indoor modular textile flooring; project performance requirements separately stated

Carpet tile backing

PVC backing 6 mm total: PVC backing 6 mm total 500 x 500 mm PP face

Asphalt backing 5 mm total: Asphalt backing 5 mm total 500 x 500 mm PP face

Carpet Tile Supply Schedule

Tile configuration: 500 x 500 mm module, selected backing/thickness and polypropylene face

Floor layout: Net room area, laying direction, perimeter cuts and agreed spare tiles

Separate items: Adhesive/tackifier, underlay, transitions and installation when specifically listed

Order and delivery: Approved face-and-backing sample, tile count, packing, destination and schedule

Configuration basis and sources

Source - https://georgebuildhub.com/products/furnishings-wall-panels/