Built-In Wet Bar Cabinets with a Sink Bay and Separate Dry Storage

Product Specification Schedule

Cabinet arrangement	600 mm sink base +900 mm three-drawer bank +900 mm closed dry-storage cupboard.
Bar cabinet finish	Oak-veneer cabinet fronts and visible ends; 20 mm white quartz top separately itemized
Nominal run and height	2400 W x 600 D x 900 H mm including the selected 20 mm top; additional room-fit fillers separately sized.
Selected plywood build	18 mm cases and shelves; 12 mm wooden drawer sides/backs; supported 6 mm backs/bottoms. Floor-bearing recessed plinth.
Sink service compartment	Paired hinged doors to the left 600 mm bay. Actual sink, support, trap and valve positions control the plumbing layout.
Dry storage and drawers	Three center drawers; right cupboard with two hinged doors and one shelf. No cooler or refrigeration bay included.
Top and connection scope	20 mm white quartz top, basin and faucet separately itemized; cutouts, sealing and plumbing follow actual selections and site scope.

Wet bar finish

Natural oak veneer: Oak-veneer cabinet fronts and visible ends; 20 mm white quartz top separately itemized

Wet Bar Cabinet Package & Separate Fixtures

Cabinet run: Sink-base case with paired doors, three-drawer unit, dry cupboard and shelf, plinth and scheduled visible panels.

Finish and fittings: Oak-veneer fronts, finished interior edges, ordinary hinges, full-extension runners and selected pulls.

Separate wet fixtures: Selected quartz top, sink bowl, faucet, backsplash if requested, and model-specific top cutouts and supports.

Delivery and site work: Packing and freight as quoted; duties, unloading, cabinet restraint, top fitting, sealing and plumbing assigned separately.

Configuration basis and sources

GEORGE Furniture Global custom kitchen and wardrobe material range - https://georgefurnitureglobal.com/product/modern-luxury-custom-kitchen-cabinets/

GEORGE Cabinetry integrated door wall cabinet system - https://georgecabinetry.com/integrated-door-wall-cabinet-system/