# Custom Bi-Fold Shower Doors with an Upper Guide Track

**Product Specification Schedule**

| | |
|---|---|
| **Door configuration** | Two inward-folding glass leaves in an alcove; wall-hinged first leaf, guided free leaf and full-width upper track. |
| **Configuration options** | Polished chrome matched hinge, hanger, connector and handle finish; compatible upper-track finish scheduled with the package; Brushed nickel matched hinge, hanger, connector and handle finish; compatible upper-track finish scheduled with the package |
| **Selected layout** | 900 mm finished wall opening; nominal 2000 mm glass height. Equal nominal split; final glass widths and installed head height by exact hardware template. |
| **Glass and processing** | Selected 8 mm monolithic tempered glass with finished edges and template-based holes made before tempering. Final glass sizes and combined mass verified with the hardware. |
| **Guided hardware** | Two wall-to-glass hinges, two glass-to-glass hinges, upper track, one hanger, wall-to-track connectors, compatible stop, pull and seals. |
| **Site interfaces** | Handing, inward fold path, parked stack, usable entry, structural wall/head fixing, threshold and water seals by accepted assembly drawing. |
| **Order scope** | Glass and each matched hardware item scheduled together. Packing, freight, site measurement, backing, waterproofing and installation separately stated. |

### Bi-fold shower hardware finish

Polished chrome: Polished chrome matched hinge, hanger, connector and handle finish; compatible upper-track finish scheduled with the package

Brushed nickel: Brushed nickel matched hinge, hanger, connector and handle finish; compatible upper-track finish scheduled with the package

### Bi-Fold Shower Door Quote Schedule

Processed glass: Two tempered leaves with scheduled finished sizes, edges, holes, handing and glass identification.

Matched movement system: Four hinges, full-width upper track, one hanger, connectors and compatible stop by exact reference and quantity.

Finish and sealing: Selected metal finish, pull, wall/center/bottom seals and threshold detail on the same assembly schedule.

Delivery and site work: Packing and freight itemized; measurement, structural backing, waterproofing, installation and adjustment individually assigned.

### Configuration basis and sources

Custom Tempered Glass Bathroom Shower Door | GEORGE Group - https://www.georgebuild.com/all-products/shower-door/

CRL Hydroslide Glass-to-Glass Hinge - https://www.crlaurence.co.uk/uk/catalog/product/view/id/75530/s/crl-hydroslide-glass-to-glass-hinge-configsku-55504/