Custom Flat Tongue-and-Groove Wood Wall Boards

Product Specification Schedule

Board configuration	Custom solid wood flat-face wall board with side tongue/groove and square ends; dry interior wall facing.
Configuration options	Selected solid oak flat-face wall boards with the scheduled T&G profile and clear finish; Selected solid pine flat-face wall boards using the same scheduled T&G profile; finish and knot range by sample
Selected size and face pitch	2400 mm square-end length; 18 mm machined body; 150 mm fully engaged dry-fit face pitch. Loose profile width 156 mm including 6 mm tongue; finished mating fit by sample.
Selected side joint	Centered 4 mm-thick tongue projects 6 mm; opposite groove 7 mm deep x 4.5 mm high. Dry-fit root allowance 1 mm and total vertical allowance 0.5 mm; actual finishing/machining checked together.
Setout and board ends	Eight 150 mm pitches = 1200 mm facing before perimeter/movement allowances. No end matching; butt joints land on support. Cut pieces and final quantities by elevation.
Finish and fixing	Actual species/grade/face range, clear finish and completed mating sample agreed. Wall, battens, orientation and timber movement determine fixing and perimeter detail.
Supply scope	Boards by finished length/quantity and accepted profile; trims, cut pieces, samples, fixing/support parts, packing, freight and installation separately scheduled.

Solid wood wall-board material

Oak boards: Selected solid oak flat-face wall boards with the scheduled T&G profile and clear finish

Pine boards: Selected solid pine flat-face wall boards using the same scheduled T&G profile; finish and knot range by sample

T&G Wood Wall-Board Quote Schedule

Wood boards: Actual timber species, grade, lengths, piece counts, flat-face profile and accepted finish.

Joint and edge work: Mating profile sample, square end cuts, cut-width boards, corners and perimeter trims.

Support and fixing: Only the agreed battens, backing and fixing parts; local wall preparation and support installation separately stated.

Packing and delivery: Long-edge protection, labeled board list and freight; site cuts and installation responsibilities individually assigned.

Configuration basis and sources

Soft Furnishing Solutions | GEORGE INTL - https://georgeintl.com/soft-furnishing/

Custom Cabinetry & Whole-Home Millwork | GEORGE INTL - https://georgeintl.com/custom-cabinet/