# Custom Laundry Cabinets with a Drawer-Mounted Folding Ironing Board

**Product Specification Schedule**

| | |
|---|---|
| **Cabinet configuration** | Laundry base cabinet with a folding ironing board in the upper drawer space and separate closed lower storage. |
| **Configuration options** | Warm-white melamine cabinet fronts on the selected plywood body; same complete drawer-space ironing-board fitting; Oak-veneer cabinet fronts on the same selected plywood body and complete drawer-space ironing-board fitting |
| **Selected cabinet fit** | 500 mm outside width minus two 18 mm sides gives 464 mm clear width. Selected 600 mm outside depth / 550 mm clear depth. Overall height by accepted worktop and fitting elevation. |
| **Selected board fitting** | Hafele Ironfix 568.60.710: unfolded board 950 L x 300 W mm; white steel fittings and white-gray striped cotton cover. Complete matched rail/support package. |
| **Required opening** | Manufacturer inside width 362-500 mm; minimum clear depth 500 mm. Selected 18 mm top panel beneath the worktop meets the original section's 19 mm maximum; upper fascia selected 18 mm thick. |
| **Body and installation** | Selected 18 mm plywood body, supported 6 mm lower-storage back and 20 mm finished worktop. Rail setting, upper-front height, stop and working height by exact fitting instructions. |
| **Order scope** | Cabinet, fronts/pulls, worktop/plinth and exact complete ironing fitting listed individually. Packing, freight and site work separate; iron and electrical work separately named. |

### Ironing-board cabinet front

Warm-white melamine: Warm-white melamine cabinet fronts on the selected plywood body; same complete drawer-space ironing-board fitting

Oak veneer: Oak-veneer cabinet fronts on the same selected plywood body and complete drawer-space ironing-board fitting

### Laundry Ironing-Board Cabinet Quote Schedule

Cabinet parts: Accepted body dimensions, plywood build, upper fascia, lower storage, selected finish, pulls, plinth and worktop.

Board fitting: Hafele 568.60.710 complete cabinet rails, extending supports, folding board, fitted cover and installation parts.

Mounting and working space: Clear opening, exact rail setting, fascia adjustment, deployed projection and final working height on the accepted layout.

Delivery and site work: Packing and freight itemized; cabinet fixing, mechanism installation and adjustment assigned. Iron, steamer and electrical work separately named.

### Configuration basis and sources

Laundry | George Cabinetry - https://georgecabinetry.com/product-category/whole-house-customization/laundry/

Ironfix Drawer Mounted Ironing Board | HafeleHome - https://www.hafelehome.com.au/products/ironfix-drawer-mounted-ironing-board